BRUHAT BANGALORE MAHANAGARA PALIKE

Office of the Executive Engineer, Rajarajeshwari Nagara Division, RR Nagara Zone, B.B.M.P., Bangalore.

Tender Notification No: RRND/EE/Ten/42/2012-13 Date: 21.01.2013

Item No. 8

SCHEDULE -B

NAME OF WORK: Improvements to drain & Construction of culverts at W type HMT qtrs in ward no 16

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	432.00	Earthwork excavation for the foundations of the buildings,water supply,sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of the pits and trenches,stacking the excavated soil clear from the excavations with lead upto 50m after breaking of clod complete a per specifications	cum	182.00	Rupees One Hundred Eighty Two Only
2	36.00	Providing sand cement bed with 5% cement with all leads for all materials and lift of 1.5m.machine mixed,laid in layers of 15cms .thick and well compacted for fondation,including curing cost of materials labour and HOM complete as per Specification	cum	1930.00	Rupees One Thousand Nine Hundred Thirty Only
3	54.00	Providing and laying in position plain cement concrete of 1 mix M7.5 with OPC cement @ 180kgs, with 40mm down size granite metal coarse aggregates @0.85cum and fineaggregtes @0.57 cum m machine mixed, machine mixed concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation and plinth, includig cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	3500.00	Rupees Three Thousand Five Hundred Only
4	140.40	Providing and constructing granite/ trap/basalt size stone masonry in basement with cement mortar 1:6,edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	2904.00	Rupees Two Thousand Nine Hundred Four Only
5	25.92	Providing and laying in position plain cement concrete of mix M15 with cement @240kgs with 20mm and down size graded granite metal coarse aggregates @0.878 cum and fine aggregates 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted, in foundation , plinth and cills, including cos of all materials, labour, HOM machinery, curing complete as per specifications	cum	3973.00	Rupees Three Thousand Nine Hundred Seventy Three Only
6	234.00	Providing flush pointing to square rubble,course or uncoursed stone masonry with CM1:3,20mm deep after raking joints to depth of 20mm nicely lining,including cost of materials,labour,currong complete as per specification	cum	65.00	Rupees Sixty Five Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರ
ರಾಜರಾಜೇಶ್ವರಿ ನಗರ ವಿಭಾಗ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ
560 054

7	108.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar 7.50 cms thick including fixing curing etc., complete.	cum	285.00	Rupees Two Hundred Eighty Five Only
8	108.00	Providing and removing centering, shuttering, strutting, propping etc,and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes,thickness upto200mm including cost of all materials,labour complete as per specifications	sqm	285.00	Rupees Two Hundred Eighty Five Only
9	74.52	Providing and laying in position reinforced cement conctrete of design mix M 20 with OPC cement @ 320kgs with 20mm and down size graded granite metalcoarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum,with super plastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed,concrete laid in layersnot exceeding 15 cms thick,vibrated for all works in foundation plinth and ground floor level for roof slabs,staircase,lintles,retaining walls,return walls,walls(any thickness) including attached plasters,columns,piers,abutments,pillars,posts,struts,buttresses,string or lacing courses,parapets,coping,bed blocks,anchor blocks,plain window cills,fillets etc.including cost of all materials,labour,HOM of machinery,curing,complete as per specifications	cum	4720.00	Rupees Four Thousand Seven Hundred Twenty Only
10	74.42	Providing T.M.T. steel reinforcemnet for R.C.C. work including straightening, cutting bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete asper design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	qtl	6598.00	Rupees Six Thousand Five Hundred Ninety Eight Only
11	344.00	Conveying the excavated earth slit debris and over burden earth etc.,to a lead of 10 to 15kms distance by using private vehicle thi include the cost of loading and unloading charges etc.,complete	cum	99.00	Rupees Ninety Nine Only

Signature of the Contractor

Executive Engineer
Rajarajeshwarinagara Division
B.B.M.P

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP